

**QUOTATION DOCUMENT**

---

Name of Bidder :

---

Sealed Quotations are invited on behalf of the Director, IISER TVM and will be received in the Office of the Project Engineer cum Estate Officer (I/C), IISER TVM Vithura campus from contractors/agencies for the following works at IISER TVM Vithura Campus, Thiruvananthapuram District, Kerala.

---

<b>Name of Work</b>	<b>PAC</b>	<b>EMD</b>
<b><i>Providing chain-link fencing Near Cricket practice court at Indoor stadium at IISER Campus, Thiruvananthapuram</i></b>	<b><i>Rs.2,33,848/-</i></b>	<b><i>Rs.4,677/-</i></b>

---

The period of completion of the work is 30 days.

The filled & duly signed Quotation Documents and Schedule of Quantities (SOQ) should always be placed in sealed cloth lined cover super-scribing the name of work will be received in the Office of the Project Engineer cum Estate Officer (I/C), IISER TVM, Maruthamala P.O., Thiruvananthapuram-695551 Up to **03.01.2023** - 16.15 Hrs and will be opened by authorized officer of IISER TVM on **03.01.2023 at 16.30 Hrs** in the presence of tenderers or their representatives who would like to be present. In case of representatives the Authorization letter should be produced to within the tender opening.

Sd/-

**Project Engineer cum Estate Officer(I/C)**  
**IISER TVM**

## OTHER TERMS AND CONDITIONS

1. The contractor shall observe all security and safety requirements of the Institute and also fulfil other statutory requirements as prescribed by the Government.
2. No facility of conveyance, lodging, food etc. shall be provided by the department.
3. In case of breach of contract at any stage, the department reserves the right to withhold the payment and take suitable action as deemed appropriate.
4. Department will not be hold responsible for any casualties via fatal or non-fatal caused for the workers etc., while inside the campus during his work.
5. Insurance coverage against fatality and medical assistance for injuries shall be the sole responsibility of the contractor and not the department. Hence no claim what so ever on these ground shall be entertained.
6. The contractor shall ensure that minimum wages are paid to their workers deployed in the campus as per the prevailing minimum wages act.
7. The Contractor shall ensure full compliance with tax laws, labour laws, etc with regard to this Contract and shall be solely responsible for the same. The contractor shall keep IISER TVM fully indemnified against liability of tax, interest, penalty, ESI, EPF, etc., of the Contractor in respect thereof, which may arise.
8. In the present scenario the contractor shall strictly follow the practice enforced by the Government as well as the Institute from time to time with respect to the Covid-19.
9. Contractor shall maintain necessary log books, registers, day to day work details, etc.
11. Performance Guarantee - 5% of tendered/accepted value. Performance guarantee deposited by the contractor shall be released after satisfactory completion of work.
12. Security Deposit - 2.5% of tendered/accepted value. Security deposit will be recovered at the rate of 5% of the gross value of the running account bills.
14. Quotations with any condition, including conditional rebates, shall be rejected.
15. GENERAL RULES & DIRECTIONS: General Conditions of Contract for CPWD Construction Works-2020 with up to date amendments (As on date of opening of price bid) shall be read with NIQ.
16. Specifications to be followed:
  - i. Specification as mentioned in the tender documents
  - ii. CPWD General specification

- iii. IS specification
- iv. Original Equipment Manufacturer's specification
- v. Engineer in Charge's decision

17. Rates quoted by the Contractor in item rate tender in figures and words shall be accurately filled in, so that there is no discrepancy between the rates written in figures and words. However, if a discrepancy is found, it will be dealt as follows:-

- i. The rate which corresponds with the amount worked out by the Contractor shall be taken as correct.
- ii. If the amount of an item is not worked out by the Contractor or if it does not correspond with the rate written either in figures or words, then the rate quoted by the Contractor in words shall be taken as correct.
- iii. Where the rates quoted by the Contractor in figures and in words tally but the amount is not worked out correctly the rate quoted by the Contractor will be taken as correct and not the amount.
- iv. In the case of any quotation where unit rate of any item/items appears unrealistic, such quotation will be considered as unbalanced and in case the contractor is unable to provide satisfactory explanation, such a quotation is liable to be disqualified and rejected.
- v. All documents of the quotation are to be read in conjunction with each other and rates quoted accordingly by the bidder.

Sd/-

**Project Engineer cum Estate Officer (I/C)**

**Name of work: Providing chainlink fencing Near Cricket practice court at Indoor stadium at IISER Campus, Thiruvananthapuram**

<b>Item No.</b>	<b>Description of Item</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate (In figures &amp; words)</b>	<b>Amount</b>
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	All kinds of soil.	1.00	Cum		
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
	For thickness of tiles above 25 mm and up to 40 mm	2.00	Sqm		
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in - charge.				
	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.50	Cum		
4	Providing and laying in position cement concrete of specified gradeexcluding the cost of centering and shuttering - All work up to plinthlevel :				

**Name of work: Providing chainlink fencing Near Cricket practice court at Indoor stadium at IISER Campus, Thiruvananthapuram**

Item No.	Description of Item	Qty	Unit	Rate (In figures & words)	Amount
	1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size).	1.00	Cum		
5	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge <i>Made of G.I. wire of dia 4 mm</i>				
	Made of G.I. wire of dia. 4 mm, PVC coated to achieve outer dia not less than 5 mm in required colour and shade	70.00	Sqm		
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer including two coats of synthetic enamel paint using structural steel etc. as required.				
	Hot finished welded type tubes	538.00	Kg.		
				<b>TOTAL =</b>	